


Diamond A

132 Church Rd
Jacksboro, TX 76458 US
(940) 229-0775
diamondaequine@hotmail.com



Estimate

ADDRESS

Jack Co Court House

ESTIMATE # 1026

DATE 08/16/2022

EXPIRATION DATE 08/30/2022

ACTIVITY	QTY	RATE	AMOUNT
Contract Work:Contract Electrician Run 2 circuits for condensers(existing circuits are undersized), Hook up condensers, Core drill wall	1	3,750.00	3,750.00
Contract Work:HVAC Two Head Mini Split System Install two indoor wall units and run freon line set with communicating wire and drains. Set outdoor unit on new pad and install voltage surge protector. Start system and check for freon leaks and check operation.	1	12,500.00	12,500.00
Contract Work:HVAC . Single Head Mini Split System Install indoor wall unit and run freon line set with communicating wire and drains. Set outdoor unit on new pad and install voltage surge protector. Start system and check for freon leaks and check operation.	1	8,750.00	8,750.00

This estimate is for the county judges offices on the second floor.
This includes line set covers if needed and any holes that need to be
bored in the walls to make access for the line sets.

TOTAL


\$25,000.00

Accepted By

Accepted Date

Diamond A

132 Church Rd
Jacksboro, TX 76458 US
(940) 229-0775
diamondaequine@hotmail.com



Estimate

ADDRESS

Jack Co Court House

ESTIMATE # 1024

DATE 08/16/2022

EXPIRATION DATE 08/23/2022

ACTIVITY	QTY	RATE	AMOUNT
Contract Work:HVAC Remove and haul off all old equipment. Set new indoor air handling unit with evaporator coil and heat kit and set new thermostat. Set new outdoor condensing unit with new pad and electrical whip and surge protector. Reconnect all freon lines and check for leaks. Reconnect all line power and control wiring and check all connections. Start system and check operation	1	13,125.00	13,125.00

This estimate is for the County Commissioners Court room. This will include replacing the wall grills as needed and making sure they are properly attached to the wall

TOTAL

\$13,125.00

Accepted By

Accepted Date