Approved 5-0
10/13/2026 10:28am

Horton Bridge & Piling
817-565-3345

10/09/2026

Formal Bid for the Roberts Branch Road Project

RECEIVED
OCT 13 2026
JACK COUNTY AUDITOR

Roberts Branch Road Bridge Replacement Proposal

Project Overview

This formal bid provides a detailed proposal for the replacement of the Roberts Branch Road Bridge by Horton Bridge & Piling. It outlines the project scope, the respective responsibilities of Horton Bridge & Piling and the County, and the associated pricing.

Scope of Services

The proposed replacement bridge will measure 24 feet by 40 feet and will be designed to an HS-20 load rating.

This bid includes all labor and materials required for the removal of the existing bridge and construction of the replacement bridge. Horton Bridge & Piling will also assist the County with constructing a traffic bypass. The County will supply all materials required for the bypass.

Horton Bridge & Piling will furnish the following materials and components:

- Piling
- Bearing plates
- Stiffeners
- Diaphragms
- Connector plates
- Deck angles
- Decking
- Side channels
- Guardrails
- Shear connectors
- Headwalls
- Wing walls
- Concrete

FILED FOR RECORD
_____ O'CLOCK _____ M
OCT 13 2026
VANESSA JAMES, County Clerk
JACK COUNTY, TEXAS
BY_____ DEPUTY

Stringer beams will be donated by Henry Birdwell JR.

Cap will be donated by Terry Ward

Horton Bridge & Piling
817-565-2345

10/09/2026

Formal Bid for the Roberts Branch Road Project

Roberts Branch Road Bridge Replacement Proposal

Project Overview

This form provides a detailed proposal for the replacement of the Roberts Branch Road Bridge by Horton Bridge & Piling. It outlines the project scope, the respective responsibilities of Horton Bridge & Piling and the County, and the associated pricing.

Scope of Services

The proposed replacement bridge will measure 24 feet by 40 feet and will be designed to an HS-20 load rating.

This bid includes all labor and materials required for the removal of the existing bridge and construction of the replacement bridge. Horton Bridge & Piling will also assist the County with constructing a traffic bypass. The County will supply all materials required for the bypass.

Horton Bridge & Piling will furnish the following materials and components:

- Piling
- Bearing plates
- Stiffeners
- Diaphragms
- Cornernor plates
- Deck angles
- Decking
- Side channels
- Guardrails
- Shear connectors
- Headwalls
- Wing walls
- Concrete

Stringer beams will be donated by Henry Birdwell JR.

Cap will be donated by Terry Ward

FILED FOR RECORD

O'CLOCK M

OCT 13 2025

VANESSA JAMES, County Clerk
JACK COUNTY, TEXAS

BY DEPUTY

Horton Bridge & Piling
817-565-3345

10/09/2026

County Responsibilities

- The County shall supply all material required for the traffic bypass.
- The County shall manage and implement any road closures required during the construction period.
- The County shall install all signage necessary for construction safety and traffic communication.

Pricing Structure

The total cost for the bridge replacement is **$3,175.00 per linear foot** of newly constructed bridge.

Total Bid: $127,000.00

Price will not exceed over $127,000.00

Validity of Bid

This bid shall remain valid for thirty (30) days from the date of issuance.

COPPELL CONSTRUCTION COMPANY, INC.
PO BOX 620
SAINT JO, TX 76265
940-995-3101

RECEIVED
OCT 13 2026
JACK COUNTY AUDITOR

9/02/2026 | Jack County | Roberts Branch Rd | Pecint 4 | Bridge Replacement

COUNTY: Jack
DISTRICT: Precint 4
PROJECT NO (Federal):
CONTRACT NUMBER:
HWY: Roberts Branch Rd
TIME: One Month
TYPE: Bridge Replacement
ESTIMATE: $233,330.00
BIDS RECEIVED UNTIL: 10/12/2026
BIDS WILL BE OPENED: 10/12/2026

ALT	ITEM NO.	DES CD.	ITEM DESCRIPTION	UNIT	APPROXIMATE QUANTITIES	UNIT PRICE	EXTENDED PRICE
	100	7002	PREPARING ROW	STA	1.00	2500	$2,500.00
	110	7004	EXCAV (ROADWAY & CHANNEL)	CY	500.00	15	$7,500.00
	247	7044	FL BS (CMP IN PLC)(TY A GR 1-2) (6")	SY	250.00	30	$7,500.00
	400	7010	CEM STABIL BKFL	CY	50.00	150	$7,500.00
	416	7005	DRILL SHAFT (36 IN)	LF	272.00	250	$68,000.00
	420	7012	CL C CONC (ABUT)	CY	50.40	950	$47,880.00
	422	7005	REINF CONC SLAB (BOX BEAM)	SF	600.00	28	$16,800.00
	425	7026	PRESTR CONC BOX BEAM (4B20)	LF	140.00	200	$28,000.00
	432	7043	RIPRAP (STONE PROTECTION)(18 IN)	CY	100.00	250	$25,000.00
	450	7004	RAIL (TY T631)	LF	75.00	40	$3,000.00
	496	7009	REMOV STR (BRIDGE 0 - 99 FT LENGTH)	EA	1.00	8000	$8,000.00
	500	7001	MOBILIZATION	LS	1.00	2500	$2,500.00
	502	7001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	1.00	1500	$1,500.00
	506	7039	TEMP SEDMT CONT FENCE (INSTALL)	LF	100.00	5	$500.00
	506	7041	TEMP SEDMT CONT FENCE (REMOVE)	LF	100.00	1	$100.00
	552	7003	WIRE FENCE (TY C)	LF	150.00	15	$2,250.00
	552	7010	WIRE FENCE (WATER GAP)	LF	60.00	80	$4,800.00
						TOTAL BID PRICE	**$233,330.00**

NOTES: PROPOSAL IS ASSUMING USING STANDARD TXDOT AND LOCAL SPECIFICATIONS, WITH TXDOT SPECS AND EXPECTATION BEING THE MINIMUM REQUIREMENT.
PROPOSAL DOES NOT INCLUDE ENGINEERED DRAWINGS, AND ONLY ASSUMES USING TXDOT STANDARDS FOR A 35 FOOT SINGLE SPAN SLAB BRIDGE.
IF PLANS OR SPECIFICATIONS ARE PROVIDED POST BID, WE RESERVE THE RIGHT TO ADJUST PRICING AS NECESSARY TO COVER COSTS.

SHADEN CLARK
EVP

10/12/26

AMTEKPRO - BID DETAILS

JACK CO - ROBERTS BRANCH ROAD BRIDGE REPLACEMENT – PRECINCT 4

Amtek ID: 1012D
Addenda: A
Estimate:
Prebid:
Pre-Bid Link/Meeting:
Bid: 10/12/2026 09:00 AM TO OWNER, OPENS 9:05 AM
Bid Opening Link/Meeting:

Arch./Eng.:
Owner:
JACK COUNTY, CO AUD, 100 N. Main St., S-202, Jacksboro, Texas 76458
940-507-0231, TERRY WARD, CO COMMISSIONER, tward@jackcounty.texas.gov

Plans: NO DOCS AVAIL - REQ INFO FRM OWNER

Notes:
NO COMP SETS TO PLANROOM

Scope:

The project generally consists of the removal and lawful disposal of the existing bridge structure and construction of a replacement bridge , including all labor, materials, equipment, transportation, site preparation, earthwork, bridge approaches, drainage improvements, traffic control, site restoration, and other work necessary for a complete project in accordance with the plans, specifications, contract documents, and applicable requirements.
The project involves an off-system bridge , meaning a bridge located on a roadway that is not part of the designated State Highway System and that is under the jurisdiction of Jack County.

Construction shall be performed in accordance with the project plans and specifications and all applicable requirements of Jack County, the State of Texas, and the Texas Department of Transportation (TxDOT) applicable to the project.

NOTE FROM OWNER: CURRENT BRIDGE IS ABOUT 18' LONG AND NEEDS TO BE 35-40' LONG.

Amtek ID	Description	Unit	Qty	Unit Price
No bid items yet.				